



NOTES:

1. ALL FENCING MATERIALS, FASTENERS TO BE GALVANIZED PRIOR TO APPLICATION OF BLACK VINYL COATING.
2. MID-BRACE RAIL TO BE LOCATED EQUIDISTANT BETWEEN TOP AND BOTTOM RAIL ON TERMINAL, CORNER, STRAINING, OR GATE POSTS.
3. WIRE MESH SHALL BE INSTALLED ON THE MUNICIPAL SIDE OF THE FENCE POSTS.
4. WIRE MESH SHALL BE MEASURED AT 9 GAUGE PRIOR TO GALVANIZING AND BLACK VINYL COATING.
5. CONCRETE FOOTINGS TO BE 20MPa STRENGTH AT 28 DAYS
6. ALL PIPE TO BE SCHEDULE 40.
7. CONFIRM GRADING PRIOR TO FENCE INSTALLATION.
8. 50MM CLEARANCE, FROM THE BOTTOM RAIL AND WIRE MESH TO FINISHED GRADE, IS TO BE CONSISTENT ALONG THE ENTIRE LENGTH TO FACILITATE MAINTENANCE.

ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE SHOWN.

**STANDARD DRAWING**

REV 1

MAY 2023

**CHAINLINK FENCE DETAIL**



**CW-805**