NOTES:

- (A) 1200 mm HIGH PAIGE WIRE FARM FENCE SECURED TO STEEL T-BARS AT MIN. 3000 mm O.C.. FENCING MUST BE STRETCHED TO ACHIEVE TENSION.
- (B) FOR SUBDIVISIONS AND ANY OTHER LONG DURATION PROJECTS (MORE THAN 1 YEAR), FENCING TO INCLUDE 2.44 m HIGH, 150 mm CEDAR POSTS LOCATED AT 21 m O.C. AND AT ALL CHANGES IN DIRECTION WHERE REQUIRED BY APPROVED VEGETATION MANAGEMENT PLAN.
- (C) EROSION/SEDIMENT CONTROLS SHALL BE AFFIXED DIRECTLY TO TREE PROTECTION FENCING WHERE LOCATIONS COINCIDE.REFER TO **EROSION CONTROL PLANS AND** DETAILS WHERE APPLICABLE. WHERE NO ADJACENT GRADING/ GROUND DISTURBANCE WORKS ARE REQUIRED ON DEVELOPMENT SIDE, EROSION CONTROL MEASURES SHALL NOT BE KEYED. REFER TO DETAIL 'A'.
 ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE SHOWN

- ATTACHMENT OF FENCE TO TREES WILL NOT BE PERMITTED.
- IF TREE ROOTS ARE EXPOSED TO AIR. ENSURE ROOTS ARE WATERED UNTIL THEY CAN BE COVERED AGAIN. ANY EXPOSED ROOTS TO BE REMOVED SHALL BE HAND PRUNED USING PROPER ARBORICULTURAL PRACTICES.
- CONTRACTOR WILL ONLY ENTER / WORK WITHIN THE TREE PROTECTION ZONE (TPZ) WHERE APPROVED BY THE CITY OF WATERLOO.
- FENCING TO BE INSPECTED ON A REGULAR BASIS AND MAINTAINED BY CONTRACTOR.
- TREE PROTECTION FENCING SHALL BE INSTALLED PER THE LOCATIONS SHOWN ON THE APPROVED VEGETATION MANAGEMENT PLAN. ONCE INSTALLED, A SITE INSPECTION WITH A REPRESENTATIVE FROM THE CITY'S ENGINEERING SERVICES SHALL BE SCHEDULED FOR APPROVALS PRIOR TO ANY WORK COMMENCING ON SITE.
- TREE PROTECTION FENCE WILL REMAIN INSTALLED FOR THE DURATION OF ALL CONSTRUCTION WORKS.

TABLE 1.0:

MINIMUM TREE PROTECTION ZONE DETERMINATION

TRUNK DIAMETER (DBH AT 1.4m)	MINIMUM PROTECTION DISTANCES REQUIRED
<10 cm	1.8 m
11 - 40 cm	2.4 m
41 - 50 cm	3.0 m
51 - 60 cm	3.6 m
61 - 70 cm	4.2 m
71 - 80 cm	4.8 m
81 - 90 cm	5.4 m
91 - 100+ cm	6.0+ m

NOTE:

MINIMUM TREE PROTECTION ZONES (TPZ) SHALL ONLY BE USED WHERE SPACE IS LIMITED AND WHERE APPROVED BY THE CITY OF WATERLOO.

STANDARD DRAWING

REV₁

MAY 2023

TREE PROTECTION FENCING



CW-701